

WINDSOR

Phone: 5199668642
1885 Provincial Road
Windsor, ON
Email: mikeb@vehicleventure.com



2023 WEBER LANE 6.5X12 DUMP 24" SIDES BARN DOOR/ RAMP FRONT MOUNT HOIST 10,000 GVWR

Stock#: 129318	VIN#: 129318	Year: 2023
Manufacturer: Weberlane	Width: 98" or 8'2"	Length: 144" or 12'0"
Height: 64" or 5'4"	GVWR: 9979	Color: BLACK
#Axles: 2		
URL: https://vehicleventure.com/2023-weber-lane-6-gB3o.html		

Price	\$11,995.00
Sales Price	\$11,295.00

Description

OVERVIEW

Contractor Level Dump trailers are built with heavy-duty construction to match the needs of professionals using these trailers day after day. The heavy gauge 3/16" steel floor plating ensures the dump trailer floor will not warp or bend under heavy use. The dual piston undermount cylinders provide absolute stability while dumping. Contractor dump trailers come in both "LP" low profile designs, with the bed tucked down low between the fenders, or the traditional deckover the wheels style to provide a better pile when dumped, and a narrower overall width. Interior strung wiring is standard on Weberlane trailers, to provide long-lasting, trouble-free wiring, whether it's used in the summer time, or the winter time with its adverse conditions of snow, ice, and slush.

FEATURES

- Spring Axles - EZE Lube Hubs
- Rear Double Barn Doors w/Cam Lock & Door Tie-Backs
- Electric Brakes
- Shielded Roll Tarp w/ Crank and Bungees
- White Modular Wheels with C6 Radial Tires
- Steel Checkerplate Fenders
- 14,000 lb Coupler for 2 5/16" Ball

7000 lb Top Wind Drop Leg jack

Safety Chains and Reflective Marking

3/16" Floor Plate

12V Electric Power Pack with Remote Control

Enclosed Electric Motor and Hydraulic Tank

Undermount Piston Cylinders

Gloss Paint Finish

All Interior Wiring

Rubber Grommet Sealed Light Package

24" High Sides plus 10" Gusset

SPECS

Overall Length: 16'

Overall Width: 98"

Overall Height: 64"

Ext. Box Length: 12'

Ext. Box Width: 78"

Box Depth: 24" + 10" Gussets

Platform Height: 28"

Hitch Weight 449 lbs

Hitch Height: 16"

G.V.W.R: 9979 lbs

Curb Weight: 2867 lbs

Payload: 7112 lbs

Axles (Tandem): 2 x 5200 lbs

Brakes: Electric 2 Axles

Tires: ST225/75R15C

Wheels: 15" 6 Bolt

Break Away Kit: Standard

null